



**Leon County**  
**Board of County Commissioners**  
301 South Monroe Street, Tallahassee, Florida 32301  
(850) 606-5302 www.leoncountyfl.gov

Purchasing Division  
2284 Miccosukee Road  
Tallahassee, Florida 32308  
(850) 606-1600

Commissioners

BILL PROCTOR  
District 1

JANE G. SAULS  
District 2

JOHN DAILEY  
District 3

BRYAN DESLOGE  
District 4

BOB RACKLEFF  
District 5

CLIFF THAELL  
At-Large

AKIN AKINYEMI  
At-Large

PARWEZ ALAM  
County Administrator

HERBERT W.A. THIELE  
County Attorney

August 31, 2009

RE: Bid Titles: Dempsey Mayo Road Sidewalk Project, BC-09-01-09-60  
Velda Dairy Road Sidewalk Project, BC-09-01-09-61  
Perkins Road Sidewalk Project, BC-09-01-09-62

**Opening Date: Thursday, September 3, 2009 at 2:00 PM**

**ADDENDUM**

Dear Vendor:

This letter serves as Addendum #4 for the Dempsey Mayo and Velda Dairy Projects, and as Addendum #3 for the Perkins Road Project.

1. Attached are revised bid pricing sheets for all three projects. These sheets are available in Excel format on the Leon county Purchasing Division website at: <http://www.leoncountyfl.gov/Purchasing/addenda/index.asp>.
2. The revisions reflect the following:
  - Dempsey Mayo - added 12" thermoplastic for cross walks, added Modified Type F curb and removed fence pay item
  - Velda Dairy - added 12" thermoplastic for cross walks and removed fence pay item
  - Perkins - added Modified Type F curb and removed fence pay item

Acknowledgment of this addendum is required as part of your bid submittal. Failure to acknowledge this addendum may result in rejection of your bid.

Should you have any questions, feel free to call me at (850) 606-1600.

Sincerely,

Keith M. Roberts  
Purchasing Director

**BIDDERS ARE NOT TO ADD OR DELETE LINES OR ITEMS FROM, NOR MODIFY THE PROJECTED QUANTITIES ON THIS PRICE WORKSHEET.** Any bid that does any modification to the worksheet will be considered non-responsive.

BID PRICING SHEET FOR SIDEWALK CONSTRUCTION AT VELDA DAIRY ROAD					
PAY ITEM NUMBER	ITEM DESCRIPTION	QTY.	UNIT	UNIT PRICE	TOTAL PRICE
101-1	Mobilization	1	LS		
102-1	Maintenance of Traffic	1	LS		
104-10-1	Hay Bales*	3,300	LF		
104-13-1	Type IV Silt Fence*	3,300	LF		
110-1-1	Clearing and Grubbing*	9,872	SY		
110-7-1	Mailbox (Furnish and Install)*	5	EA		
120-1	Excavation Regular*	2,000	CY		
120-2-2	Excavation Borrow (Truck Measure)*	1,000	CY		
120-6	Embankment*	200	CY		
142-70	Sand Fill*	145	CY		
400-1-2	Concrete Class I (Endwall)*	5	CY		
430-174-125	Pipe Culvert Opt. Material Class II (18")*	22	LF		
430-984-125	Mitered End Section (18")*	4	EA		
443-71-1	Ballast Rock, French Drain Aggregate*	945	CY		
514-71-1	Filter Fabric, Plastic*	7,300	SY		
515-2-201	Pedestrian Railing, Steel, 42" Picket Rail	100	LF		
522-1	Sidewalk (4" Thick) w/ fiber mesh added	3,203	SY		
520-110	Modified Type F Curb	1,130	LF		
527-1	Detectable Warning (Truncated dome mat)	16	EA		
575-1-2	Sodding (Centipede)	9,872	SY		
577-70	Shoulder Re-Work*	500	SY		
700-46-21	Sign, Existing (Relocate)*	4	EA		
711-11123	Thermoplastic, Standard, White, Solid 12"	180	LF		
LC-001	Final Dressing	1	LS		
LC-002	Construction Layout/Surveying	1	LS		
LC-010	Tree Protection*	2,300	LF		
				<b>TOTAL COST=</b>	

ANY WORK REQUIRED BUT NOT SPECIFICALLY LISTED, SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT, AND SHOULD BE INCLUDED IN THE MOST APPROPRIATE PAY ITEM ABOVE.